

SAMPLE PROJECT - SANDBOX FIXTURE

DRAWING: S2.0 | FRAMING PLAN - LEVEL 02 | SCALE: 1/8" = 1'-0"

BUILDING DIMENSIONS: 120'-0" x 60'-0" x 14'-0" eave

GRID: A-G x 1-7 | 20' bays both directions

STRUCTURAL STEEL: ASTM A992 W-shapes, ASTM A500 Gr.C HSS, ASTM A36 plate/angle

COLUMN SCHEDULE

Mark	Shape	Qty	Length (ft)	Weight (lb/ft)	Total (lbs)
C1	W12X40	14	14.0	40	7,840
C2	W14X53	8	14.0	53	5,936
C3	HSS6X6X1/2	6	14.0	35.2	2,957

BEAM SCHEDULE (Level 02 Framing)

Mark	Shape	Qty	Length (ft)	Weight (lb/ft)	Total (lbs)
B1	W18X35	18	20.0	35	12,600
B2	W21X44	12	20.0	44	10,560
B3	W24X62	6	30.0	62	11,160
B4	W16X26	20	20.0	26	10,400

OPEN-WEB STEEL JOIST SCHEDULE (Roof)

Mark	Type	Qty	Span (ft)	Spacing (ft)
J1	20K7	30	30.0	5.0
J2	24K9	18	40.0	5.0

ROOF DECK: 1.5" Type B, 22 ga, SDI-certified, 120'-0" x 60'-0" = 7,200 SF

ANCHOR BOLTS: ASTM F1554 Gr.55, 3/4" diameter x 18" embed, qty: 4 per column = 112 rods total

CONNECTIONS: ASTM A325 Type 1 bolts, shop fabrication per AISC 360-22, AISC 303-22 standards. Bolted shear connections at all beam-column joints.

NOTES:

1. Steel fabrication shop drawings required per AISC 303-22 prior to fab.
2. PE-stamped shop drawings + erection plan required.
3. Anchor bolts set by foundations contractor to Nano Cube setting plan.
4. Inspection fees by Owner per IBC 2021 Ch. 17.
5. AESS classification: NONE. All steel shop-primed only.
6. Cold-formed metal framing (Div 05 40/41) by others.

This is a SANDBOX FIXTURE for VJ takeoff testing only. Not a real construction document. No PE stamp, no scale, no detail.

MEMBER LIST (canonical takeoff form)

W12X40: 14 each @ 14'-0" (C1 columns)

W14X53: 8 each @ 14'-0" (C2 columns)

HSS6X6X1/2: 6 each @ 14'-0" (C3 corner columns)

W18X35: 18 each @ 20'-0" (B1 floor beams)

W21X44: 12 each @ 20'-0" (B2 floor beams)

W24X62: 6 each @ 30'-0" (B3 transfer beams)

W16X26: 20 each @ 20'-0" (B4 spandrels)